

SOITEC | More light, more life.



Installation instructions



Bioclimatic Pergola

Agava SL

Prefix

This Installation Instructions manual offers you the know-how on assembling and mounting Soltec Pergola Agava SL System. Through reading process you will notice, that this quide is made through following the basic knowledge presented in Soltec's Training quide.

This manual is focused on the first 14 points from the Training Guide.



- Acceptance of goods, inspection of documentation, visual inspection of cargo and confirmation in CMR documentation.
- 2. Opening of the box and inspection of the components on the basis of packing list and relevant documentation, preparation of tools and mounting equipment.
- 3. Marking the location on the floor or wall for mounting the structure and fixing the brackets.
- 4. Knowledge of the frame composition for freestanding pergola or pergola with wall fixation. Joints of corners and posts, fixation of frame to the bracket and frame to the wall. Checking the inclination of the frame structure according to the instructions.
- 5. Joining of the electrical cables before the frame assembly and circuit testing.
- 6. Knowledge of sliding insertion technology, connecting blades to the drive axle/bar and the setting of end points. Knowledge of mechanical endpoint correction technology on oval holes.
- 7. Connection of the blades with/to the LED lights.
- 8. The option to mount the cover in case of non-standard length of the pergola (concave or convex shape of tin sheet).
- 9. The option of mounting fixed roof integration (installation of roof glass or aluminum sheet).
- 10. Installation of ZIP roller blind, guides, cassette, end points, electrical cable joints.
- 11. Installation of sliding panels, guides.
- 12. Installation of glass panels, guides.
- 13. Electrical connection of the pergola to the home network, motor self-test and test drive. Sealing all joints with MERBENIT glue or SIKA 553. Client training using a pergola and presentation of operating instructions.
- 14. Regular annual maintenance (inspection of operation, engine reset self-test, inspection of seals, + cleaning of water channels, inspection or necessary replacement of plastic parts, protection of rubber seals, cleaning of the pergola).


Index

5	Configurations						
6	STEP18	STEP 2	Check received cargo				
7		STEP 2.1	Read the instructions				
8		STEP 2.2	Tools & Equipment				
9		STEP 2.3	Order Form				
13		STEP 2.4	Marking the location				
14	STEP 3		Positioning				
16		STEP 3.1	Parallelism of wall and profile				
17	STEP 4		The place needed for assembling the installation				
18	STEP 5		Inserting metal plates into wall mounting frame profile				
19		STEP 5.1	Inserting metal plate for supporting post on position P5				
20		STEP 5.2	Screwing and inserting the L - angle upper (AA) into				
			transverse frame profile				
21		STEP 5.3	Screwing and inserting the L - angle lower, connecting &				
			with threads (AC) into transverse frame profile				
22		STEP 5.4	Screwing and inserting the L - angle lower (AB) into				
			transverse frame profile				
23		STEP 5.5	Metal plates, L - angles (AA), (AB), (AC) and screws (A)				
			are in place				
24	STEP 6		Connection of electrical and signal cables through				
			the profiles				
25		STEP 6.1	Connecting the cables and sockets				
26		STEP 6.2	Assembling of the frame and testing of cable connections				
28	STEP 7		Screwing a longitudal frame profile and L - angles				
28		STEP 7.1	Screwing a longitudinal frame profile and upper L - angle				
28		STEP 7.2	Screwing a longitudinal frame profile and lower L - angle				
			(positions P1, P3, P4)				
29		STEP 7.3	Longitudinal frame profile and lower L - angle				
			(position P2 - with post)				
30	STEP 8		Position of foot support (example type frame)				
30		STEP 8.1	Inclination of the frame				
31		STEP 8.2	Tabel info				


Index

32	STEP 9		Attachment of pedestals					
33	STEP 10		Laying frames on posts					
34		STEP 10.1	Screwing the post on position P2					
35		STEP 10.2	Screwing the post on position P5					
36	STEP 11		Attaching the frame to the wall					
37	STEP 12		Screwing the post and foot support					
38	STEP 13		Assembly of blades					
39		STEP 13.1	Inserting the blades					
41		STEP 13.2	Inserting the blades with connecting wire rope					
42		STEP 13.3	Inclination of blades					
44	STEP 14		Connection of blades to drive bar					
44		STEP 14.1	Adjustment of closing of the blades					
45		STEP 14.2	Self-test - Self learning of limit switches					
47		STEP 14.3	Remote control, settings and management					
48		STEP 14.4	Connecting the sockets and testing integrated LED lights					
49	OPTIONS	5	ZIP roller blind					
51			Rain Sensor					
52			Wind Sensor					
54			Temperature sensor with wiring - Mounting					
55			Sliding panels (glass, aluminium & wooden slats)					
56	ITEM LIS	TTYPE 2						
60	ATTACHN	MENTS (Ele	ectric plans)					
60			Pergola SL & Motor DC24V					
61			Motor DC24V & LED & ZIP					
62			Motor DC24V & LED					
63			Motor DC24V & LED & ZIP Somfy Motor					
64			Pergola SL & Heater					
65	LIST OF SERVICE INSPECTIONS							
68	CONTACT	г						


Configurations




TYPE 1 Self-standing




TYPE 5 Wall-mounted blades parallel to wall




TYPE 2 Wall-mounted blades perpendicular to wall




TYPE 6 Self-standing posts off-center




TYPE 3 Wall-mounted on two sides blades perpendicular to wall




TYPE 7 Wall-mounted blades perpendicular to wall



TYPE 4 Wall-mounted blades parallel to wall



TYPE 8 Wall-mounted blades perpendicular to wall



EXAMPLE TYPE

The TYPE G configuration is used in Installation instructions to present all the possible situations in the process of installation of pergola.




CMR documentation example


Check received cargo

Acceptance of goods, inspection of documentation, visual inspection of cargo and confirmation of CMR documentation

- · Inspect all documents
- · Check for possible cargo damage and REPORT it in CMR documentation
- · SIGN and STAMP the acceptance of package and parts in CMR documentation
- Make a confirmation of CMR documentation



STEP 2




Packing list example

Check received cargo

Opening the box and inspection of the components on the basis of packing list and relevant documentation, preparation of tools and mounting equipment

- · Opening the box
- · Check and inspect the components, using the packing list



Read the instructions

Before beginning with installation, you MUST go through following points


- **1.** The amount of pieces in the received assembly
- 2. The quality of the pieces in the received assembly
- 3. Installation Manual
- 4. User Manual
- 5. Warranty statement

BEFORE YOU START

- to install the product, you MUST read carefully Pergola Agava Price list, especially marked OBLIGATORY! and Pergola Agava Instructions Manual.
 - Read the suggested documents
 - Follow the instructions







Instructions Manual

STEP 2.2

Tools & Equipment

Using the right Tools & Equipment for the job is essential for good installation and for avoiding potencial injuries.



Ring - Fork Key 10mm, 13mm, 17mm



Screwdriver Philips & flat blade



Hex / Imbus keys 3mm, 4mm, 6mm, 8mm



Electric hand drill machine



Drill bit Ø10, Ø12




Laser measure or/and gauge



Hand meter



Pencil / Marker



Spirit level




Working gloves



Helmet and protecting glasses



Lifting Pads




Standing Pads



Ladder

Watch Soltec videos on Youtube channel:



- 1. Go to Google Play or AppStore
- 2. Download QR Reader aplication
- **3.** Open the aplication and scan QR Codes in this
- **4.** Watch installation instructions videos





STEP 2.3

Client

Order Form

With Order Form, the buyer specifies all the essential specifications of Agava Pergola. The specific model is precisely defined in Order Form and this document is the basis of every Agava Pergola project.

Project

Step 1 / Client information


Name		Name			Name				
Address		Address			Date				
					Requested date of delivery (week)				
Phone		Phone)						
E-mail		E-mail	-						
With signoff of this Order Client declares, that the Oread and accepts the Ger and Conditions of Soltec are published on www.sc	Client has neral Terms d.o.o., which oltec.si.		np & signature						
Step 2 /	Produc	ct in	formation)					
Type of pergola	Type of i	nstallat	ion	D	imensions (specify in mm)				
☐ Agava SL 160/28		Type 1	Type 5)					
☐ Agava SL 170/28		- 0							
☐ Agava SL 170/36		Type 2	2 Type 6)					
☐ Agava SL 240/36		Type 3	3 👗 🗆 Type 7	7	нЕІСНТ				
☐ Agava SL 240/60		91			#				
Quantity of Pergola		Type 4	Type 8	3	1 1				
Number					WOTH LENGTH				
Number of poles	Height of pe	rgola	Colour						
☐ O poles	P1		Standard						
☐ 1 pole	P2		STRUCTURE grey	acon	white DB 703				
☐ 2 poles	P3		anthracite RAL 7016	grey aluminiur RAL 9008	n traffic micro-				
☐ 3 poles	P4		BLADES		^ _				
☐ 4 poles	Hight of pergola 3-3 possible only with a		grey anthracite RAL 7016	grey aluminiur RAL 9006					
additional pole:	foot mounting. Extra cost of higher		•	10.2000	V 18.200.0				
	and external foot m is 160 €.	ounting	Non-standard Subject to additional payment.						
			STRUCTURE RAL no.	BLADE RAL no					
			IVAL HU.	Tipis!	J.				


Deliver to (when different)

Order Form

Step 3 / Drawing with marked specifications

Mark motor position, water exit and power supply on top view







location of power supply




location of water exit



- \cdot Water exit is possible on same pole as electricity, but only if Type P is ordered as special option of water evacuation.
- · Pergola must have min. 2 water exits!
- · Position of cutting is on pole foot.

Blades opening way



LED lights

A) LED lights integrated into the blades

B) LED strip lights

Length of LED (m)

RGB


Position of LED lights (mark on drawing)

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46

Order Form

Step 4 / Options

ZIP blinds



Position

- □ P1 P2
- □ P1 P3
- □ P3 P4
- □ P2 P4

Fabric Serge

- ☐ 108101 grey-white
- ☐ 108108 grey
- ☐ 108118 grey-black ☐ 116101 linen-white
- ☐ 117101 pearl-white
- □ 117117 pearl

Fabric Soltis

+ 10%

Crystal full screen

+10%

Crystal window

dim.


Motor

- standard
- Somfy

Colour of guides

- Same as pergola frame
- ☐ Different RAL NO.

Sliding panels




Position

- □ P1 P2 □ P3 - P4
- □ P1 P3 P2 - P4

Sliding type

Colour / Standard



grey anthracite RAL 7016

grey aluminium RAL 9006 ■ white traffic RAL 9016



Type

Number of panels

Dimension of panels (width in mm)


Colour /

Non-Standard

Subject to additional payment +10%.

RAL no.

Glass panels




Position

- □ P1 P2 P3 - P4
- □ P1 P3 P2 - P4

Folding type

- 2 panels / 2 guides ☐ 4 panels / 2 guides
- 6 panels / 3 guides



Colour / Standard

- grey anthracite RAL 7016
- grey aluminium RAL 9006
- ☐ white traffic RAL 9016

Number of panels

Dimension of panels (width in

mm)

Colour /

Non-Standard

Subject to additional payment +10%.

RAL no.

Order Form

Step 5 / Accessories

Sensors	Sound system	Remote control	Heater Heliosa			
Rain sensor	Number of speakers	Quantity	Quantity			
□ Wind sensor□ Snow sensor (Rain + Temperature sensor)□ Temperature sensor□ Presence sensor	☐ Audio system☐ Audio system + Bluetooth	☐ Teleco / 42-channels☐ Somfy / 4-channels☐ Somfy / 1-channel☐ T-mate APP☐ Daisy APP☐	☐ White☐ Anthracite			
Wall mounting Fe	oot mounting	External foot	Position of holes on			
standard	standard (inox) / internal	mounting protection	profile for wall fixation			
optional P1 P3 P2 P4	optional / external	galvanizationgalvanization + paintinginox	drill the profile (indicate on drawing)no drilling (client ensures power supply)			
■ Type A / Convex type ■ Type B / Concave type Step 7 / Ha	Type E and drawing		3 / Additional			
with marke	d specifical	tions comm	ents			
		To be filled b	y Soltec / manufacturer			
		Value				
		Shipping				
		In total				
		Offer number				
		Project referer	nce number			
		Date				

SOLTEC d.o.o. • Obrtna ulica 9 • 8257 Dobova, Slovenia **T** +386 (0)7 45 27 126 • **E** info@soltec.si • **www.soltec.si**


STEP 2.4

Marking the location

Marking the location on the floor or wall for mounting the structure and fixing the brackets is also the start of mounting process.

There are practically 8 basic possibilities of mounting, which can be seen in the Configurations on page 5.

The Example Type explained in this Installation Instructions Manual is shown below.



Example type model is shown with correlating positions and helping lines.

Positioning


Position of the wall mounted frame profile & foundation position

Before starting to assemble the frame, it is necessary to determine the position of the longitudinal frame profile on the wall and foundation positions:

- Use a laser gauge/laser measure to indicate the X3 line on the wall.
- If needed, use a spirit level to mark a proper 0°.
- 3. Lean the profile to the wall.
- The positions of the anchor bolt holes shall be indicated/drawn for mounting the profile on the wall. Indicate positions P3 and P4 on the wall with a marker.
- Indicate the foundation positions.


post positions support lines for positioning width of profiles height of profiles length of profiles D1, D2 length between diagonal pergola corners **X3** support line for P1, P2, P3, P4 **P5**

wall profile corners of frame construction support with post, dislocated from corner




^{*} Follow the instructions from "Price List 2020"

Positioning



EXAMPLE TYPE


Top view



STEP 3.1

Parallelism of wall and profile

BEFORE starting to assemble the frame, check the parallelism between the wall and the wall profile. If curvedness is too large, mounting the frame is not possible.




The place needed for assembling the installation

Put four pedestals on a suitable place, big enough for assembling.

Pedestals MUST be coated to avoid damage on the profiles.


Remove all unnecesary obstacles.




Inserting metal plates into wall mounting frame profile

- Metal plates (R) are inserted into the wall mounting profile
- The number of plates depends on the project (position P3, P4)
- Align plates with anchor bolt axis

PHASE 1 Corner P3 and P4







Inserting metal plate for supporting post on position P5

Metal plate (Y) is inserted into the longitudal profile for supporting post on position P5.

PHASE 1





PHASE 2


P5




Screwing and inserting the L - angle upper (AA) into transverse frame profile


L-angle upper (AA) is inserted into all 4 transverse frame profile corners

PHASE 1







PHASE 2



Screwing and inserting the L - angle lower, connecting and with threads (AC) into transverse frame profile






Screwing and inserting the L - angle lower (AB) into transverse frame profile


1. **L-angle lower (AB)** is inserted into transverse frame profile corner P2.

Corners with a post support only need L-angle lower (AB).

PHASE 1




P4 (on right side)



Metal plates, L - angles (AA), (AB), (AC) and screws (A) are in place

- L angle upper (AA)
- L angle lower, connecting and with threads (AC)
- L angle lower (AB)
- metal plates P3, P4 (for wall fixation)
- metal plate P5

- 1. Inserted **L-angle upper (AA)** are succesfully inserted into the corresponding places.
- Inserted L-angle lower, connecting & with threads (AC) are successfully inserted into the corresponding places.
- 3. Inserted **L-angle lower (AB)** are succesfully inserted into the corresponding places.
- **Metal plates** are inserted into the wall mounting profile on positions P3 and P4.
- **Metal plate** is inserted into the longitudinal profile on postion P5.
- **6.** The assembly is prepared as shown below.



Connection of electrical and signal cables through the profiles



BEFORE

continuing the installation, all electrical and signal cables must be connected and tested.



All these processes have to be performed on the pedestals.

Before beginning the testing, **OPTIONS chapter** in the installation instructions must be read.

Connection of cable connections is carried out when the frame profiles are not screwed together.

Blades motor unit and LED lights are preset in the factory. ZIP roller blind is not preset in the factory. Preset of ZIP roller blind should be done by installer.


After completing the installation, the metal constructions must be grounded.

POSITION 1

- **Blade motor:** Connect plug and socket on **AG** joint
- 2. **LED Light:** Connect plug and socket on **AF** joint

POSITION 2

1. **LED Light:** Connect plug and socket on **AF** joint



STEP 6.1

Connecting the cables and sockets

1. BLADE MOTOR UNIT

Connect plug and socket on AG joint





2. LED LIGHT

POSITION 1

Connect plug and socket on AF joint

AF joint is properly connected, if the inscription "ALTW" on the connectors is visible on the same side.





3. LED LIGHT POSITION 2

Connecting of plug and socket on AF joint is made in STEP 14.1, after inserting the blades.





4. ZIP ROLO

POSITION 1

Connect plug and socket on AH joint Wires of the same colors are connected to each other



STEP 6.2


Assembling of the frame and testing of cable connections



1. ASSEMBLING OF THE FRAME

Both transverse frame profiles (W1, W2) are evenly and at the same time inserted into a longitudinal frame profile.

CAUTION: The cables in frame must not be damaged.






2. CONNECTION TO ELECTRICAL VOLTAGE

When the frame is assembled, the power cord (3 \times 1,5 mm²) is connected to the electrical voltage.

ATTENTION: Only a trained person can carry out the connection.





N: neutral

L: phase

G: ground




3. TESTING ZIP ROLLER BLIND

Check the rolo movement UP and DOWN.

The final setting is done when the frame is set on location.

Use remote control, follow instruction in OPTIONS chapter.





4. DISCONNECTING POWER

After finishing testing, you must disconnect the power supply.




Screwing a longitudal frame profile and L - angles

STEP 7.1

Screwing a longitudal frame profile and upper L - angle (positions P1, P3, P4)

Through openings on longitudinal profiles, profile and upper L-angle are screwed together with **A screws**.




STEP 7.2

Screwing a longitudinal frame profile and lower L - angle connecting and with threads (positions P1, P3, P4)

Through openings on longitudinal profiles, profile and lower L-angle connecting and with threads are screwed with **B screws**.

Repeat at position P1, P3, P4 (these positions are wall mounted or without posts) In position P5, the lower L - angle will be screwed together with the post.




STEP 7.3

Longitudinal frame profile and lower L - angle (position P2 - with post)

Through the middle oval hole in the lower part of the frame the lower L-angle is attaching to the frame with **C screws** from below to prevent the L-angle from moving before screwing the post.

In position P2, the lower L - angle will be screwed together with the post in STEP 10.




Position of foot support (EXAMPLE TYPE frame)



T1, T2 - Position of foundations (AD) under posts


NOTE: D1 = D2

Use a laser gauge. Tighten the screws of assembled frame, when the diagonals are properly set.



STEP 8.1

Inclination of the frame



STEP 8.2

Tabel info



Use this list for height differences.

Respect the values for different Pergola models and Type of Installations.

FRAME INCLINATION (in mm) has to be performed by installer

WIDTH OF PERGOLA


	Blade incl. in frame [mm]	1500	2000	2500	3000	3500	4000	4500	5000	5500	6000
Agava SL 160 / 28	0	5	5	10	15	20	30	/	/	/	/
Agava SL 170 / 28	9	0	0	0	5	10	20	/	/	/	/
Agava SL 170 / 36	6	0	0	0	0	5	10	15	/	/	/
Agava SL 240 / 36	9	0	0	0	0	0	5	10	/	/	/
Agava SL 240 / 60	9	0	0	0	0	0	0	5	5	10	10



ZIP roller blind, panels or glass

NOT POSSIBLE INSTALATION ON WIDTH

Attachment of pedestals





DRILLING AND INSERTING SCREW E

- 1. Drill into the foundation through the diagonal pair of holes. Use a drill for concrete with a diameter of 12 mm.
- 2. Insert screw E into the foundation holes.

NOTE: Rotate the pedestal according to posts drainage opening.








Laying frames on posts

LIFTING POSTS



- 1. Lift the composite profiles using lifting pads.
- 2. Place the posts on their position and screw them. Do not forget to use your protective equipment.
- 3. It is necessary to pay attention to the correct position and orientation of the posts.

Check your plans and your order.




STEP 10.1


Screwing the post on position P2



SCREWING THE LOWER L - ANGLE WITH A SUPPORTIVE POST (P2)

- 1. Use the **screws B** and screw the lower L angle with post.
 - It is necessary to have a hexagonal key, to be long at least 20 cm.
- Openings on the upper side of the frames, seal with plastic bushes P.
 The bonding edges can be sealed with adhesive. Use the Merbenit MB55 adhesive.





P1, P2, P3, P4

STEP 10.2

Screwing the post on position P5

SCREWING THE PLATE FOR POST OUT OF THE CORNER WITH A SUPPORTIVE POST (P5)





Do not forget to use your protective equipment.

- Seal the openings on the upper side of the frames with plastic bushes P. The bonding edges can be sealed with adhesive. Use the Merbenit MB55 adhesive.
- 3. It is necessary to pay attention to the correct position and orientation of the post.

Check your plans and your order.







Attaching the frame to the wall










The frame is raised and leaned to the wall, then the profile of the frame is fastened (P3, P4). **Do not forget to use your protective equipment.**

The frame must be supported by the pedestals until the fixing to the wall is completed.

The **R plate** was inserted into the profile in STEP 5.

To drill the hole to the wall, use **drill Ø 12.**

Use anchor **bolts E** for fixing profile to the wall.



STEP 12


Screwing the post and foot support








- The post is placed on **foot support AD**. There are two holes **M10** in the foot support.
- **Two holes** must be drilled into the **post**. The positions of the holes are adjusted to the conditions at the installation site. Check the positions of the holes M10 on the foot support!
- After the post is placed on foot support, **screw A** is screwed to fix post and foot support.

The post must be grounded on floor.










STEP 13

Assembly of blades

The blades are inserted into a structure and standing frame.

First, insert the blades at both ends of the structure.




STEP 13.1

Inserting the blades

The long axis of the blade is inserted into the profile with motor drive.

The long axis of the blade is on the side of the blade where the cover with "ear" is located.




Inserting the blade

POSITION 2

Position after installing the longer axis (kingpin) I in the motor drive frame.


The shorter axis (kingpin) K of the blade is then inserted into the opposite lying coaxial opening.



POSITION 2


Position 2 of the blade when both axis are inserted into the frame.

Place a distance plastic bush N around the longer axis (kingpin)



POSITION 3

After installing the **distance plastic bush,** move the blade in the direction of the longer axis. On the side of the shorter axis there should be a space of **3-4 mm** between the blade and the frame.




STEP 13.2

Inserting the blades with connecting wire rope

If the frame is longer than $\bf 4 m$, some blades have reinforcement bindings inserted into their axis.

Number of those blades depends on the lenght of **L1, L2 profiles**.

Positions of these blades are determined by service holes **(1)** on the top of the longitudinal frame profile.



Inclination of blades


For water to outflow properly, the blades must have a certain inclination.

The inclination of the blades differs between different Pergola Agava models.

160/28

The difference in blades position height is **0 mm**.


The inclination of the blades can be achieved by inclining the frame (STEP 8.1 and 8.2)



170/28

The difference in blades position height is **9 mm**.


The blade is declining from Drive unit side.



170/36

The difference in blades position height is $\mathbf{4.5}\ \mathbf{mm}$.


The blade is declining from Drive unit side.



240/36


The difference in blades position height is ${\bf 5}~{\bf mm}.$

The blade is declining from Drive unit side.



STEP 14

Connection of blades to drive bar



STEP 14.1

Adjustment of closing of the blades






- 2. Move the inox profile **1 mm** from the center towards the corner of the pergola, where the blades are not fully closed.
- Fasten the blades with **L-screws** and Make **"self-test"**.
- For security reason we suggest to block alu bar and inox plate together with **M6** screw and nuts.

STEP 14.2

Self test - Self learning of limit switches

When you fix screws, make a "self-test" on Remote Control.


1. Press **P** and hold it about 10s until it's signalled by a sound.





DO NOT change the DIP configuration. This change would be signalled by a new intermittent sound and flashing of L3 on Teleco driver and would require a new configuration procedure.

2. Motor 1 and Motor 2 configuration.




If the "self-test" failed and blades dont open and close correctly, you have to set them manually.

Move the rotating lever 5 to the both end positions 6.


Follow the instructions for driving the drive (Chapter G).

Finally leave your lever in a vertical position.




ADJUSTING THE SCREW


Adjust the special step screws (L) by moving them on to the left or right.



STEP 14.3

Remote control, settings and management






STEP 14.4

Connecting the sockets and testing integrated LED lights

- 1. **LED LIGHT**Connecting of plug and socket on **AF** joint.
- 2. TESTING LED LIGHTS


 Use the remote control and follow the instructions, OPTIONS chapter. Check if all LEDs are ON and OFF. When testing is complete, disconnect the connectors (AF).

 BB blades have integrated LED lights.



ZIP ROLLER BLIND

Front view




Guides of the **roller** 1 left and right, must be fixed on the **posts** 2


Use self-tapping screw.

The outer side of the post and the outer side of the guide must be in the same plane.

Section view A-A



Section view B-B



ZIP ROLLER BLIND

soltec


- ① Open **ZIP roller blind Cassette**, that is mounted on the profile.
- 2. Locate the **setting tool** with and + point.

TOP AND BOTTOM LIMIT SETTINGS: ZIP Rolo setting stick is used with electric drill machine to adjust TOP and BOTTOM Points.

- Use the remote control to lower ZIP roller to its available highest Point.
- Insert the stick into the adjustment point + and screw it to lower roller to its TOP Point.
- 5. Use the remote control to lower ZIP roller to its available lowest Point.
- 6. Insert the stick into the adjustment point and screw it to lower roller to its **BOTTOM**Point



RAIN SENSOR





White wire (12V) Blue wire (signal) 10 Yellow wire (ground) 11 The rain sensor set contains a **sensor with** wiring 1 and fastening elements 2


Rain Sensor is mounted on a suitable surface that is completely exposed to rain (for example, the upper surface of the frame for the blades).

Signal cable in the sensor 3 is connected to the control unit 4 located in the W - profile.

Wires in the cable must be connected at the appropriate coupling points.







WIND SENSOR


The wind sensor set contains a **sensor with** wiring 1 and fastening elements 2

Wind Sensor is mounted on a verticale surface. The location of the accommodation must not be in the shelter.


Signal cable in the sensor 3 is connected to the control unit 4 located in the W profile.


Blue wire 77
Brown wire 8

Wires in the cable must be connected at the appropriate coupling points.



WIND SENSOR





TEMPERATURE SENSOR

with wiring - Mounting


The sensor is placed in a suitable place. It can be inserted into the profile from the frame.


The location of the accommodation must not be in the shelter. The sensor is designed to alert you to low temperatures.

Signal cable in the sensor 1 is connected to the control unit 2 located in the W profile.

Black wire 14 White wire 15

Wires in the cable must be connected at the appropriate coupling points.







SLIDING PANELS

Glass, Aluminium & Wooden slats

Detailed assembly of Sliding panels is explained in a separate Manufacturing Guide.

ITEM TYPE LIST 2

	Number of pieces	Mark on the sketch			
Longitudinal frame profile with motor and holes for blades length = L with components: - motor unit, - drive unit inside the profile, - drive batten with screws Ø10/M6 x 19 and washers M6	1	L1			
 cover plates for service holes for motor & connecting wire ropes with screws M5 x 10 cables with connectors AG, AF, AH plastic bushes. 					
Longitudinal frame profile without motor and with holes for blades length = L	1	L2			
with components: - cover plates for service holes for connecting wire ropes with screws M5 x 10 - plastic bushes		LZ			
Transverse frame profile with service hole length = W					
with components: - control unit for motor - cover plate with screws M5 x 10 - cables with connectors AG, AF, AH - transformator 220 - 24V - control unit for ZIP roller blind or heater or LED light, if it is in order	1	W1			
Transverse frame profile length = W	1	W2			
Post with components: - ALU and stainless steel plate welded to the post for screwing a post to the frame	2				

	Number of pieces	Mark on the sketch	
Blade with components: - kingpin long and short - blade covers - sealing rubber	n1		
Blade with LED light with components: - kingpin long with holes for cable - kingpin short - blade covers - sealing rubber - LED light, cable and connector	n2		
Blade with connecting wire rope with components: - kingpin long and short with holes for wire rope - blade covers - sealing rubber - wire rope - nuts M6 self-locking hex - washers M6 large flat	n3		
L-angle upper	4	AA	
L-angle lower	2	АВ	
L-angle lower, connecting & with threads	2	AC	
U - support stainless steel foots	2	AD	
Metal plate for supporting post	1	Υ	•
Metal plate for fixing the frame to the wall ALU	m	R	0

	Number of pieces	Mark on the sketch	
Screw M10 x 20 inbus round head with collar	26	А	
Screw M10 x 35 inbus socket head cap	18	В	
Screw M6 x 16 inbus round head with collar	4	С	
Anchor bolt M12 x 135	4 + m	Е	
Distance plastic bush	n	N	(
Rubber washer	2		
Plastic caps Ø18 for screw holes	18	Р	
Plastic caps 5/4" for wall fixation holes	m	Q	


n - number of blades

m - number of holes in the wall

	Number of pieces	
Remote control	1	
Rain sensor	1	
Wind sensor	1	
Temperature sensor	1	


Electric plans

Pergola SL + Motor DC24V




Electric plans

Motor DC24V + LED + ZIP




Electric plans

Motor DC24V + LED




Electric plans

Motor DC24V + LED + **ZIP Somfy Motor**



Electric plans

Pergola SL + Heater



LIST OF SERVICE INSPECTIONS

Type of product	Date of service inspection	Signature, Stamp
Type of product	Date of service inspection	Signature, Stamp
<u> </u>	•	
Tues of acadust	Data of comics is says that	Signahusa Sha
Type of product	Date of service inspection	Signature, Stamp
Type of product	Date of service inspection	Signature, Stamp
Type of product	Date of service inspection	Signature, Stamp
	-	
Tues of acadust	Data of comics is says that	Signatura Sta
Type of product	Date of service inspection	Signature, Stamp
Type of product	Date of service inspection	Signature, Stamp

-							



2-year warranty on electronic equipment and components

5-year warranty on the structure of Pergola Agava™

5 year warranty, made in EU, fully certified



SOLTEC d.o.o.

Obrtna ulica 9 8257 Dobova Slovenia, EU

+386 7 45 22 126

+386 51 650 850

info@soltec.si

www.soltec.si











To ensure optimal quality, Pergola Agava is in accordance with the following EN standards:

EN 1990: **Basis of Structural Design**

EN 1991: **Actions on structures**

EN 1991-1-1: General actions - Densities, self-weight, imposed loads for

buildings

EN 1991-1-3: General actions - Snow loads EN 1991-1-4: **General actions - Wind actions** EN 1991-1-5: General actions - Thermal actions

EN 1993: **Design of steel structures** FN 1998 Design of structures for earthquake resistance

EN 1999: Design of aluminium structures

EN 1090: **Execution of steel and aluminium structures** EN 13561: External blinds and awnings. Performance requirements

including safetu

EN 60335-1: Household and similar electrical appliances - Safety - Part

1: General requirements

EN 60335-2-97: Household and similar electrical appliances. Safety.

Particular requirements for drives for rolling shutters, awnings, blinds and similar equipment